

# Status MAX IV



Åke Andersson & Aleksandar Mitrovic

On Behalf of the MAX IV RF Group


Sven-Olof Heed, Dionis Kumbaro, Lars Malmgren, Aleksandar Mitrovic,  
Per Lilja, Robert Lindvall, David Olsson

FOJAB arkitekter SNØHETTA MAXLAB: Skiss 110609

# Outline

- MAX IV overview
- Status MAX IV - Linac
- Status MAX IV – 3 GeV Ring
- Status MAX IV – 1.5 GeV Ring

# MAX IV overview




Inauguration was June 21, 2016

# MAX IV Facility Overview

- Facility can accommodate up to 32 user beamlines: 3 @ SPF, 10 @ 1.5 GeV SR, 19 @ 3 GeV SR
- 14 have been funded in our first two beamline phases


## Status

- User delivery for the 3 GeV ring & SPF, 16h/7days, resumed this week, after a 3 month SD.
- We will serve 9 BLs during the rest of the year.
- 5 in the 3 GeV ring
- 1 in the SPF
- 3 in the 1.5 GeV ring



# MAX IV linac


- The S-band linac is used as an injector for both the 1.5 and 3 GeV storage rings and the SPF (Short Pulse Facility).
- A thermionic RF gun (injection) & A photo RF gun (SPF & injection)
- 15 klystrons plus SLEDs drive the first 30 linac structures
- 2 klystrons plus SLEDS drove the last 8 linac structures
- Now



## Some bad surprises during October:



Damaged RF window in K02 – need to replace Klystron, rebake and recondition



Leaky RF window in K06 – need to replace Klystron, rebake and recondition



# MAX IV Ring RF System

## Storage Rings Parameters


Energy	1.5 GeV	3.0 GeV
RF	99.931 MHz	99.931 MHz
Circumference	96 m	528 m
Harmonic number	32	176
Current	500 mA	500 mA
No of cavities	2	6
RF station power	60kW	120kW
Cavity voltage	280kV	300kV
Coupling (beta)	2.3	4.0



1 single 60 kW transmitters

Solid State Amplifiers


2 combined 60 kW transmitters



# Ring RF System - 3 GeV Ring

Alternative	I	II
Energy loss with $I_{ds}$	756keV	1020keV
Circulating current	0.5A	0.5A
Total beam power	378kW	510kW
Total RF voltage	1.5MV	1.8MV
Number of cavities	6	6
Cavity shunt impedance	3.2Mohm	3.2Mohm
Cu losses	117kW	169kW
Total RF power needed	495kW	679kW
Nr of RF stations	6	6
Nr of transmitters	12	12
Transmitter power	41.5kW	56kW
Power to cavity	83kW	113kW
Cu losses/cav	20kW	28kW
Coupling (beta)	4.2	4.0
Cavity voltage	250kV	300kV
Cavity gap	4cm	5cm
Bucket height	4.5 %	4.5 %

Chosen!



Alt I: Represents a solution for a 60% ID equipped ring, with the present MAX II/ MAX III cavities.

Alt II: Represents a solution for a fully ID equipped ring, with slightly modified MAX II/MAX III cavities.



# Cavities in the 3 GeV ring



Photo courtesy S. C. Leemann

LABORATORY

# Status 3 GeV - Storage Ring

## Before shutdown in July:

- Delivered regularly 50 mA beam to the beam lines. Five user beam lines, but only two have external users.
- Top-up interval several hours since gating is necessary (simple dipole injection kicker)
- The wiggler beam line could not close the gap due to overheating of a chamber part downstream the wiggler, hit by the ID light.

### RF related:

- Longitudinally unstable beam above 120 mA due to HOM driven coupled bunch instabilities. The Bunch-by-Bunch feedback system (DimTel) had a very weak longitudinal actuator.
- No good setting yet found for full lengthening (\*5) with HHCs, only stable operation up to roughly twice the natural bunch length.
- One main cavity show vacuum spikes at nominal field levels, when it sees stored beam above ca 50 mA.
- Beam survives a trip, but we need to re-adjust the BbB feedback.

# Status 3 GeV - Storage Ring

## During shutdown August to October:

- Installation of a Multipole Injection Kicker (MIK). Collaboration with SOLEIL. Should allow more transparent injection and more frequent top-up.
- The chamber part downstream the wiggler exchanged.


### RF related:

- Installation of a waveguide loaded longitudinal kicker cavity. To be used by the Bunch-by-Bunch feedback system, opposing the HOM driven CBIs.
- We continuously ran the 5 main cavities in the 3 GeV ring during evenings and nights for further conditioning. We settled for approximately 250 kV (0.93\*Kilpatrik limit).
- One 120 kW circulator failure, even though < 35 kW. Exchanged.

# Status 3 GeV - Storage Ring

## RF related:

- Installation of a waveguide loaded longitudinal kicker cavity. To be used by the Bunch-by-Bunch feedback system, opposing the HOM driven CBIs.



Courtesy Dr. David Olsson

PhD Thesis: Design and implementation of RF kickers in MAX IV

ISBN: 978-91-7753-350-4 (electronic version)

<https://lup.lub.lu.se/search/publication/79fd33b7-9557-417a-bb52-1e938d7286d6>

# Status 3 GeV - Storage Ring

## Start-up in November:

- Verified that the Multipole Injection Kicker (MIK) chamber do not heat up due to 70 mA of stored current. No time yet for pulsing and injection tests.
- The chamber part downstream the wiggler was verified not to heat up.

## RF related:

- The waveguide loaded longitudinal kicker cavity was connected as actuator to the Bunch-by-Bunch feedback system. Stable beam verified up to 50 mA, at which current the users have settled for the first weeks.
- Out of the 5 main cavities in the 3 GeV ring we still have difficulties with one, once it sees currents above ca 50 mA.

# Ring RF System - 1.5 GeV ring

Case	Lund	Krakow
	I	II
Energy loss with Ids	130keV	150keV
Circulating current	0.5A	0.5A
Total beam power	65kW	75kW
Total RF voltage	0.56MV	0.5MV
Number of cavities	2	2
Cavity shunt impedance	3.2Mohm	3.2Mohm
Cu losses	49kW	39kW
Total RF power needed	114kW	114kW
Nr of RF stations	2	2
Nr of transmitters	2	2
Transmitter power	28.5kW	28.5kW
Power to cavity	57kW	57kW
Cu losses/cav	24.5kW	19.5kW
Coupling (beta)	2.3	2.9
Cavity voltage	280kV	250kV
Bucket height	4.0%	3.5%




Table 1: Two anticipated RF scenarios for the 1.5 GeV ring.

# MAX IV 1.5 GeV - Storage Ring

## Before shutdown in July:

- No delivery to beam lines, since commissioning scheduled till August 2017.
- Top-up at at 170 mA with stable beam was achieved spring this year.

## RF related:

- Longitudinal stability with help of the HHCs alone, 200 mA - 120 mA. Behavior very similar to the SOLARIS case with decaying beam. No Bunch-by-Bunch longitudinal kicker cavity yet foreseen.



# MAX IV 1.5 GeV - Storage Ring


## Before shutdown in July:

- No delivery to beam lines, since commissioning scheduled till August 2017.
- Top-up at at 170 mA with stable beam was achieved spring this year.

## RF related:

- Longitudinal stability with help of the HHCs alone, 200 mA - 120 mA. Behavior very similar to the SOLARIS case with decaying beam. No Bunch-by-Bunch longitudinal kicker cavity yet foreseen.
- Calibration:

Calibration measurements Landau 15



On resonance:

$$V_{\text{cav}} = I * (R/Q) * Q_{\text{meas}} * F$$



# MAX IV 1.5 GeV - Storage Ring

## During shutdown in August to October:

- Five new ID chambers (NEG coated), and front-ends, installed.
- Three IDs installed.

### RF related:

- We continuously ran the two main cavities in the 1.5 GeV ring during evenings and nights for further conditioning. We settled for approximately 250 kV (0.93\*Kilpatrick limit).



# MAX IV 1.5 GeV - Storage Ring

## Start-up in November:

- Injection efficiency verified to be similar as before the new ID chambers were installed.
- Top-up at 140 mA verified

### RF related:

- Vertical stability achieved with an uneven filling pattern (see below). Due to worse vacuum conditions at start-up an even fill resulted in ion trapping and vertical blow-up.  $I \cdot \tau = 800$  mAh at present. Fast conditioning.



# Thank You



Photo Perry Nordeng